



# AVINOR NORGE

KUNNGJØRINGSTJENESTEN FOR  
LUFTFARTEN  
POSTBOKS 150  
2061 GARDERMOEN

TEL.....+47 81 53 05 50  
AFTN.....ENAVHGOX  
E-mail..... aim@avinor.no

## AIP SUP

12/10  
22 MAR

12

### ANLEGG SARBEIDER VED TRONDHEIM LUFTHAVN, VÆRNES - ENVA

I perioden MAR 2010 til NOV 2012 vil det periodevis foregå anleggsarbeider ved rullebane, taksebane og sikkerhetsområder ved Trondheim lufthavn, Værnes.

Anleggsarbeidene omfatter flytting av RWY 09 vestover, etablering av utvidede sikkerhetsområder og nye lysanlegg. Arbeidene omfatter blant annet følgende hovedelementer:

- RWY 09 flyttes 150 M mot W.
- Det etableres ny LOC 27.
- GP 09 flyttes N for RWY.
- Det etableres nye rullebanekantlys.
- Ny THR 09 lyssettes med wingbar iht. BSL E 3-2.
- Sikkerhetsområdet utbedres til 75 M planert del til begge sider for RWY C/L og 300 M etter baneende.
- Montering av markeringslys for senterlinje på RWY.
- Montering av markeringslys for siktepunkt i RWY.
- Montering av PAPI i nye posisjoner, tilpasset ny THR RWY 09.
- APCH LGT RWY 09 tilpasses ny THR.
- Det etableres ny TWY til ny avgangsposisjon for RWY 09.
- MET utstyr i vest flyttes N av RWY.
- Terreng langs rullebane planeres.
- Det etableres skilter, rullebanevarsellys og stopp bars for TWY N av RWY.

### WORK IN PROGRESS AT TRONDHEIM AIRPORT, VÆRNES – ENVA

During the period MAR 2010 to NOV 2012 construction work will take place at Trondheim Airport, Værnes on and close to RWY, TWY and safety areas.

The construction work will comprise of moving RWY 09 to the W, establishment of extended safety areas and new lighting systems. This includes the following main elements:

- RWY 09 will be moved 150 m W.
- Establishment of new LOC 27.
- GP 09 will be moved N of RWY.
- Establishment of new RWY edge lights.
- Establishment of new THR 09 with wingbar lights according to BSL E 3-2.
- Safety area will be levelled in an area extending 75 M on both sides of RWY C/L, and 300 M after RWY END.
- Establishment of marking LGT for RWY centre line lights (RCLL).
- Establishment of marking LGT for RWY aiming point.
- Establishment of PAPI in new position, adjusted to the new THR RWY 09.
- Extending APCH LGT RWY 09, according to new THR.
- Establishment of new TWY to take-off position RWY 09.
- MET equipment in the W will be moved to the N of RWY.
- Terrain surface along RWY will be levelled.
- Establishment of signs, RWY guard lights and stopp bars for TWY N of RWY.

Anleggsarbeidene forventes ikke å påvirke ordinær rutetraffic, utenom ved planlagte stengeperioder som følger:

- Nattstenging av lufthavna MAR-JUN 2010, ref. AIP SUP 16/09.
- Etablering av ny RWY 09, MAY-NOV 2012. Stengeperiode vil bli kunngjort via egen AIP SUP.

Detaljer vedrørende stenging og andre aktiviteter i forbindelse med anleggsarbeidene, samt endringer i denne AIP SUP, vil publiseres via NOTAM.

- Slutt -

The construction work is anticipated to have no effect on scheduled air traffic, except when RWY is closed as follows:

- Night closure of Trondheim airport MAR-JUN 2010, ref. AIP SUP 16/09.
- Establishment of new RWY 09 MAY-NOV 2012. Closure period will be published via separate AIP SUP.

Details concerning closure and other activities related to the construction work, including changes to this AIP SUP, will be published via NOTAM.

- End -